



2009

Domestic Scan of

Accelerated

Construction Practices





Objective

Agencies are seeking ways to accelerate project delivery.

You hear about:

“Get in, Get out, and Stay Out.”

The scan focus was on how to accomplish that dictum rapidly.

Objective

From actual construction experiences identify:

- Construction practices that speed project delivery.
- Management practices that minimize the duration of work zone occupation.



Overview

- The Scan Approach
- Successful Projects & Keys to Success
- The Fundamentals
- Conclusions



SCAN TEAM

George Raymond
Oklahoma DOT

Chris Schneider
FHWA, HQ

Steven DeWitt
**NC Turnpike
Authority**


Brian Blanchard
Florida DOT

Richard Sheffield
Mississippi DOT

Stuart Anderson
Texas A&M

Thomas Bohuslav
Texas DOT

Clifford Schexnayder
Arizona State University



Projects Visited



Russian River Bridge



I-40 Mojave Desert



**I-15 Repave
I -5 Tunnel Fire Repair**



Accelerated Bridge Construction, Utah

**I-880 MacArthur Bridge
YBI Viaduct Bay Bridge**

**I-65/59 Bridges,
Birmingham**

**Duval St. Bridge
& SR9A/I-295,
Jacksonville**

**Escambia Bay Bridge, I-10
(Emergency & Rebuild), Pensacola**

I-10 Houston

Queen Isabella Causeway



Acceleration Focus Areas

- **Acceleration related to emergency projects**
 - emergency situation response
- **Project/Program construction acceleration**
 - a planned approach

Acceleration Focus Question Areas

- 1. General Program Level Issues**
- 2. Contracting Strategies/Contract Administration**
- 3. Planning and Scheduling**
- 4. Construction Practices – Cost, Time, Quality**
- 5. Traffic Control and Management**
- 6. Post-Construction
– WHAT DID HAPPEN.**




Emergency Acceleration

Acceleration is often in response to an accident or unexpected event. Projects accelerated under emergency situations have very compressed schedules yet they still have to be delivered following sound design, construction, and management processes.

This is the challenge!



Hurricane Ivan, Pensacola, Florida Night of Sept. 15/16, 2004



I-10 Bridge

Escambia Bay



Hurricane Ivan, Night of Sept. 15/16


| Date 2004 | Event |
|------------------|--|
| 17 Sept. | 9:00 a.m. Pre-proposal meeting, Chipley, FL |
| 17 Sept. | 1:00 p.m. Questions and Answer meeting |
| 17 Sept. | 4:00 p.m. Price Proposals |
| 17 Sept. | 4:00 p.m. Public Price Proposal open |
| 17 Sept. | 5:00 p.m. Anticipated Execution Date |
| 17 Sept. | 5:00 p.m. Notice to Proceed |
| 11 Nov. | Phase 1 complete, Westbound Bridge |
| 16 Dec. | Contract Completion |

Escambia Bay Bridge

**Acrow
prefabricated
steel bridge
system**

Looking West

**All designs had to conform
to the available materials.**





Keys to Success

- ***Delegated Contract Award and Execution to Local FDOT Office*** – This fast tracked the signing of a contract.



Escambia Bay Bridge, contract



6/4
deterioration of shoreline or roadway ~~is~~ ^{extremely} ~~not~~ our responsibility. No erosion control measures have been included.

- ② We understand that Phase I is to be completed (as in "open the bridge to traffic") in 24 days; liquidated damages of \$250,000/day will apply after that. Incentive bonus for opening the bridge to traffic also equals \$250,000/day up to a max. of 14 days

- ⑤ ~~We understand that the 24 day schedule is developed by the owner on the basis of his quantities~~



Keys to Success

- ***Basic Scope Only*** – Contractors need latitude about means and methods on these types of projects.
- ***Work Concurrent with Design*** – The design has to utilize available materials.



Keys to Success

- ***Availability of Materials***
 - Hard to find materials during the early phase of the work.

Birmingham, Alabama

Saturday morning

January 5, 2002



I-65/I-59 Bridge after the fire



I-65/I-59 Bridge

Day

| | | |
|---------|--|-----------|
| 5 Jan. | Saturday morning accident | 1 |
| 6 Jan. | Decision a new bridge and select five contractors. | 2 |
| 7 Jan. | Monday Start design | 3 |
| 8 Jan. | Tuesday, Prelim. Plans to Contractors | 4 |
| 14 Jan. | Monday 1:00 p.m., Pre-Bid | 10 |
| 16 Jan. | Wednesday 10:00 a.m., bids | 12 |
| 18 Jan. | Friday, Notice to Proceed | 14 |
| 21 Jan. | Monday 12:01 a.m., Construction begins | 17 |
| 27 Feb. | Opened to traffic | 54 |



***27 Feb. 2002
Opened to traffic***



54 Days after the accident



Keys to Success

- ***Partnership*** – Decisions were made at the **Project Level**: verbal requests and approvals.
- ***Mutual Trust*** – Contractor/ALDOT/Girder Fabricator





Keys to Success

Cooperation – Rapid turn around of shop drawings.

Planning – Very detailed planning and schedule.

San Francisco

**Sunday
April 29, 2007**

I-580/880




**MacArthur Maze,
Oakland**

I-80 Bay Bridge

I-580 connector

I-880 connector





MacArthur Maze

Day

| | |
|---|-----------|
| 29 Apr. Sunday, 3:41 a.m. tanker accident. | 1 |
| 30 Apr. Caltrans locating steel, begin design. | 2 |
| 1 May Clean-up, inspection | 3 |
| 3 May I-580 contract advertised. | 5 |
| 5 May Mandatory onsite bid conference. | 7 |
| 7 May Monday, bid 10a.m., award 3:30 p.m. | 9 |
| 10 May Penn. steel arrives fabricator in AZ | 12 |
| 11 May Begin girder fabrication | 13 |
| 15 May Precast bent cap arrives at night | 17 |
| 24 May Thursday, opened at 8:40 p.m. | 26 |



Keys to Success

- ***Availability of Materials*** –
Design to available materials.
- ***Team Effort*** –
Located people where needed.

Keys to Success

- ***Incentive/Disincentive*** –
The project was advertised with a \$200,000 per day incentive/disincentive clause capped at \$5,000,000.





Planned Acceleration


Projects can be accelerated

- by careful planning of preconstruction activities and
- thoughtful staging of field operations

I-15 Devore Corridor, California

Planned

Construction Zone





Keys to Success

- ***Contract*** –
Incentive/Disincentive
provisions
- ***Design*** –
Rapid-strength concrete
and substituted AC base





Keys to Success

- ***Public Outreach*** – Intensive outreach achieved a 20-percent reduction in peak-hour traffic demand

Duval Street Bridge, Jacksonville, Florida





Keys to Success

- ***Partnering –
Decisions and commitments
were made and upheld***
- ***Demand services
remediation contract –
to handle site contamination***

Keys to Success

- ***Delayed construction start –***
A six month “procurement period.”
- ***Up front planning –***
Level of detail in the contractor’s schedule.



Program Approach to Project Acceleration

Some agencies are beginning to institutionalize project acceleration through a program approach.

A change in agency culture is required as well as a new paradigm





Utah DOT Accelerated Bridge Construction (ABC)

UDOT accelerated its program for the following reasons:

- Reducing turn around times
- Lessening the impact of their projects
- Improving trust
- Response to public desire



New UDOT Paradigm

From

“Lowest Construction Cost”

to

“Lowest Project Cost”

UDOT ABC Stats

UDOT has 17 projects, including **80 bridges total**, completed or under construction that utilized ABC

- Self Propelled Modular Transports 4 projects/13 Bridges
- Half Thickness Precast Deck Panels 2 Projects/47 Bridges
- Prefab Bridges – “Lego Bridges” 2 Projects
- Full Depth Precast Deck Panels 8 Projects/11 Bridges
- Precast voided slabs 1 Project/2 Bridges
- Segmental Bridges 1 Project/1 Bridge
- Heavy Lift Cranes 1 Project/1 Bridge



UDOT ABC SPMT

- 1st SPMT Project (I-215 at 45th South) completed in 1 weekend during 2007
- 12 Additional SPMT Projects completed in 2008.
- ABC used as standard practice for future projects.





BENEFITS OF USING ABC

- Reduce **TRAFFIC** impacts
- Improve **SAFETY** to workers and public
- Improve **QUALITY** of constructed product



BENEFITS OF USING ABC

- **COSTS** savings
- Reduced **ECONOMIC** and Business impacts
- Reduced **CONSTRUCTION SEASON**
- Reduced **ENVIRONMENTAL** impacts

Success Fundamentals

- **Partnering**
- **Design**
- **Planning**
- **Contracting Strategy**



Success Fundamentals

Partnering – People are
the critical element in
successfully accelerating
a project.



Partnering

- ✓ Align goals
- ✓ Delegate
- ✓ Timely decisions



Success Fundamentals

Design –

✓ *Material Availability*

✓ *Logistics*





The fundamentals

Planning –

- ✓ ***Detailed***
- ✓ ***Backup plans***
- ✓ ***Plan multiple fronts***
- ✓ ***Look-ahead plans***



The fundamentals

Contracting Strategy –

- ✓ Aligned *with requirements*
- ✓ Set an aggressive
schedule *with proper
incentives*



Conclusions Emergency Projects

Contractor –

Find a contractor that has the resources

Experts –

Ensure that experts are on the project



Conclusions Emergency Projects

Agreement –

Get an agreement

Delegate –

To the lowest possible level

Scope –

Expect changes



Conclusions

DOT and contractor **goals align** when a **partnering** atmosphere is created and all team members view the accelerated work as an **opportunity to demonstrate excellence.**

A photograph of a large fire at night, likely an industrial or construction site. A massive plume of black smoke rises from the fire, which is intense and bright orange. Several firefighters in reflective gear are visible in the foreground, working to contain the fire. The scene is dark, with the fire providing the primary light source. The text "Thank You!!" is overlaid in large, bold, orange letters at the top. Below it, the text "We can Build Faster!" is overlaid in large, bold, green letters.

Thank You!!

**We can
Build Faster!**